BRUHATH BANGALORE MAHANAGARA PALIKE

DRAFT TENDER SCHEDULE -B

NAME OF WORK: Patching pot holes in main and cross roads of Kodigehalli, tatanagara, Bhadrappa layout, devinagara, lottegollahalli, muneshwaranagara and surroundings areas in ward no. 8

Sl.No	Qty	Description	Unit	Sanctioned rate (in Rs)
1	186.60 153.74	Earth work excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications complete as per specifications MORTH chapter 3. Page No. 141 / Item No. 19.1/ PWD SR 2015-16	Cum	83.16
2	93.22 76.79	Providing, laying spreading and compacting graded stones aggregate to wet mix macadam specifications including premixing the material with water at OMC in mechanical mix plant carriage of mixed method of tipper to site, laying, in uniform layers with paver in sub base course on well prepared surface and compacting with vibratory roller to achieve the desired density complete as per MORTH specification NO. 406, Page No. 157 / Item No. 20.18 / PWD SR 2015-16	Cum	1713.96
3	859.15 803.85 336.60	Filling Pot-holes and patch repairs with bituminous concrete, 40 mm, KSRRB M3000-5, Removal of all failed material, trimming of completed excavation to provide firm vertical faces, cleaning of surface, painting of tack coat on the sides and base of excavation as per clause 500.3 back filling the pot hole with bituminous material as per clause 500.4 compacting, trimming and finishing the surface to form a smooth continuous surface, all as per clause 3004.2 complete as per specifications, MORTH specification No. 3004.2, No. 250 / Item No. 35.5 PWD SR 2015-16	Sqm	370.44 305.64
4	299.00	Lead and disposal of Item No.1 & Road side debris	Cum	110.24

ಕರಡು ಟೆಂಡರ್ ಷಡ್ಯೂಲ್‌ನ್ನು
ಶಿದ್ಧಪಡಿಗಳ ಸಂಖ್ಯೆನ್ನಾಟ್ಟು (04)
ಶಿದ್ಧಪಡಿ ~~ಮಾಡಿ~~
ಅನುಮೋದನೆ ನೀಡಿಲಾಗಿದೆ

Chief Engineer
Yelahanka Zone
Bruhath Bangalore Mahanagara
Palike
Bangalore 92

Executive Engineer
Byatarayanapura Division
B.B.M.P Bangalore

3/11